

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
	Var. 20°15' E.	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 17 & 20	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.88	Intersect Sec. line, 24 lks. S. of Cor. to Secs. 16, 17, 20 & 21	
	S. 89° 50' W. on true line bet. Secs. 17 & 20	
39.94	Set charred stake, with mound, trench and pits as per in- structions, for $\frac{1}{4}$ Sec. Cor.	
51.00	Ravine, N. 70° W.	
79.88	Cor. to Secs. 17, 18, 19 & 20	
	Soil; some what sandy, 2nd rate.	
	<hr/>	
	Closing Cor. being in sight, run	
	S. 89° W. on true line bet. Secs. 18 & 19	
40.00	Set charred stake, with mound, trench and pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.	
86.41	Intersect Range line at post Cor. to Secs. 18, 19 R. 30, & 13, 24 R. 29 E.	
	Soil; 2nd rate.	
	<hr/>	
	September 13th	
	N. on line bet. Secs. 17 & 18	
40.00	Set charred stake, with mound, trench, and pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 7, 8, 17 & 18	
	Var. 20° E.	
	Soil; on this mile, very sandy.	
	<hr/>	
	E. on random bet. Secs. 8 & 17	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.60	Intersect Sec. line, 54 lks. S. of Cor. to Secs. 8, 9, 16, 17.	
	S. 89° 36' W. on true line bet. Secs. 8 & 17.	