

Exterior Lines of T. 5 N., R 31 E., W.M.
 As surveyed by Wm. H. Odell & Wm. S. Lewis, U.S. Deputy Surveyors
 Under Contract No. 110
 Dated Feb. 7, 1865.

Chains	March 15, 1865.	Feet
	Commenced the survey of the First Standard Parallel N. of Base Line and E. through Rs. 31, 32, 33, 34, 35, 36 & 37, bet. Tp. 4 & 5 N. at the N. E. Cor. of T. No. 4 N., in R. No. 30 E. of W. M.	
	Thence	
	E. on S. Bdy. of Sec. 31, T. 5 N., in R. 31 E.	
	Var. 20° E.	
40.00	Set Standard Cor. for $\frac{1}{4}$ Sec. Drove charred stake and dug pits & constructed mound as per instructions.	
73.00	Dry gulch, course N.W	
80.00	Set post, Standard Cor. for Secs. 31 & 32 Drove charred stake and raised mound with pits as per instructions. This line passes over rolling grounds. Good grass, no timber Soil; 2nd rate.	
	<hr/>	
	E. on S. Bdy. of Sec. 32, T 5 N R 31 E.	
	Var. 20° E.	
40.00	Set Standard Cor. for $\frac{1}{4}$ Sec. Drove charred stake and raised mound with pits and per instructions.	
80.00	Set Standard Cor. for secs. 32 & 33, on level; drove charred stake and raised mound with pits as per instructions. This line passes over rolling ground, Good grass Soil; 2nd rate.	
	<hr/>	
	E. on S. Bdy. of Sec. 33, T 5 N R 31 E	
	Var. 20° E.	
40.00	Set Standard Cor. for $\frac{1}{4}$ Sec. Drove charred stake and raised mound as per instructions.	
80.00	Set Standard Cor. for Secs. 33 & 34, on land sloping to the S.E.; drove charred stake and raised mound with pits as per instructions.	