

Exterior Lines of T. 4 N., R. 31 E., W.M. (E. Bdy.)
 As surveyed by Wm. H. Odell, U.S. Deputy Surveyor
 Under Contract No. 110
 Dated Feb. 7, 1865.

Chains		Feet
	Commenced the survey of the exterior lines of T. No. 4 N., R. 31 E., W.M.	
	May 4th, 1865	
	N. on E. Bdy. of Sec. 36, T 3 N R 31 E.	
	Var. 20°45' E.	
40.00	Set $\frac{1}{4}$ Sec. post Cor., on side hill sloping to the N.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 25, 36, 30 & 31, on top of ridge sloping to the W.; drove charred stake, dug pits, and raised mound as per instructions. This line passes over high rolling grounds. Good grass. Soil; 2nd rate.	
	N. on E. Bdy. of Sec. 25, T 4 N R 31 E	
	Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post Cor. on top of ridge; drove charred stake, dug pits and raised mound as per instructions	
80.00	Set post cor. for Secs. 24, 25, 19 & 30. Set post on right bank; drove charred stake, dug pits and raised mound as per instructions Land; broken Good grass Soil; 2nd rate.	
	N. on E. Bdy. of Sec. 24, T. 4 N R 31 E.	
	Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post Cor. for Secs. 18, 19, 13 & 24. Head of gully, S side. Drove charred stake, dug pits & raised mound as per instructions. Land; rolling Grass good,	