

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
	run	
	N. bet. Secs. 35 & 36.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 25 & 26, 35 & 36; drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
E. on random bet. Secs. 25 & 36		
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.63	Intersected N. and S. line, 25 lks. S. of post Cor. S. 89° 49' W. on true line	
39.81	Set post Cor. for $\frac{1}{4}$ Sec. on brink of ravine, course S.W.; drove charred stake, dug pits and raised mound as per instructions.	
79.63	To post Cor. Land; broken, good grass Soil; 2nd rate.	
N. bet. Secs. 25 & 26		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits, & raised mound as per instructions. Land at Cor. slopes to the S.W.	
80.00	Set post Cor. for Secs. 23, 24, 25 & 26, on E. side of ravine, course N.E.; drove charred stake, dug pits & raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
E. on random bet. Secs. 24 & 25		
		Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post cor.	
79.71	Intersected N. & S. line, 23 lks. S. of post Cor. S. 89° 50' W. on true line	