

7.
Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
39.85	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions. Stage station brs. N.20° E., about 10 Chs.	
79.71	To post Cor. Land; broken, good grass Soil; 2nd rate.	
N. bet. Secs. 23 & 24		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits, and raised mound as per instructions.	
57.00	Stage Road from Boise City to Umatilla City, course N.W.	
80.00	Set post cor. for Secs. 13, 14, 23 & 24; drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
E. on random bet. Secs. 13 & 24 Var. 20°30' E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post cor.	
79.80	Intersect N. & S. line, 32 lks. S. of post Cor. S. 89° 40' W. on true line	
39.90	Set post Cor. for $\frac{1}{2}$ Sec.; drove charred stake, dug pits and raised pits as per instructions.	
79.80	To post Cor. Land; broken, grass good Soil; 2nd rate.	
N. bet. Secs. 13 & 24		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 11, 12, 13 & 14; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass. Soil; 2nd rate.	