

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
79.76	To post Cor. Land; broken, good grass. Soil; 2nd rate.	
<hr/>		
N. bet. Secs. 14 & 15		
39.00	Stage Road, course N.W. & S.E.	
39.50	Bottom of ravine, course N.W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 10, 11, 14 & 15; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
<hr/>		
E. on random bet. Secs. 11 & 14		
Var. 20° 30' E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.85	Intersected N. & S. line, 40 lks. S. of post Cor. S. 89° 43' W. on true line	
39.92	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.85	To post Cor. Land; broken, excellent grass. Soil; 2nd rate.	
<hr/>		
N. bet. Secs. 10 & 11		
40.00	Set post Cor. $\frac{1}{4}$ Sec.; drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post Cor. for Secs. 2, 3, 10 & 11; drove charred stake dug pits and raised mound as per instructions. Land; rolling, good grass. Soil; 2nd rate.	
<hr/>		
E. on random bet. Secs. 2 & 11		
Var. 21° E.		