

## Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.94	Intersected N. & S. line, 33 lks. S. of post Cor. S. $89^{\circ} 46'$ W. on true line	
11.50	Bottom of ravine, course N.W.	
39.97	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.94	To post Cor. Land; broken, good grass. Soil; 2nd rate.	
N. bet. Secs. 2 & 3		
40.00	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits & raised mound as per instructions.	
67.50	Bottom of ravine, course N.W.	
80.39	Intersected 1st Standard Parallel N., 22 lks. W. of Post Cor. for Secs. 34 & 35, T. 5 N., R. 31 E.; set post for Closing Cor. for Secs. 2 & 3, drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
August 11th, 1866.		
N. bet. Secs. 33 & 34		
2.00	Ravine, course N.W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 27, 28, 33 & 34; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
E. on random bet. Secs. 27 & 34		
Var. $21^{\circ}$ E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.00	Intersected N. & S. line, 32 lks. N. of post.	