

## Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
	raised mound as per instructions.	
79.82	Intersected 1st Standard Parallel N., 52 lks. W. of Standard Cor. for Secs. 32 & 33, T. 5 N., R. 31 E.; set Closing Cor. at point of intersection, for Secs. 4 & 5; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
		August 12, 1866.
	<hr/>	
	N. bet. Secs. 31 & 32	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. (on level), drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 29, 30, 31 & 32, on land sloping to the N.W.; drove charred stake, dug pits and raised mound as per instructions.	
	Land; rolling, good grass	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 29 & 32	
		Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.15	Intersected N. & S. line, 71 lks. N. of post Cor. N. 89° 30' W. on true line	
25.65	A small spring, brs. N., 1.00 Chs.	
30.00	Bottom of Ravine, course N.W.	
40.07	Set post Cor. for $\frac{1}{4}$ Sec. Cor.; drove charred stake, dug pits and raised mound as per instructions.	
80.15	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	<hr/>	
	W. on random bet. Secs. 30 & 31	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.61	Intersected N. & S. line, 10 lks. S. of post Cor. S. 89° 56' E. on true line.	