

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.70	Intersected N. & S. line, 68 lks. N. of post Cor. N. $89^{\circ} 31'$ W. on true line	
39.85	Set post Cor. for $\frac{1}{4}$ Sec. on bank of ravine, course N.W.	
79.70	To post Cor. Land; broken, good grass Soil; 2nd rate.	
W. on random bet. Secs. 6 & 7		
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.43	Intersected N. & S. line, 25 lks. N. of post Cor. N. $89^{\circ} 49'$ E. on true line	
39.43	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.43	To post Cor. Land; broken, grass good Soil; 2nd rate.	
N. bet. Secs. 5 & 6		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
61.00	Bottom of ravine, course N.W.	
79.61	Intersected 1st Standard Parallel N. 77 lks. W. of post, Standard Cor. for Secs. 31 & 32, T. 5 N., R. 31 E. ; at point of intersection, set Closing Cor. for Secs. 5 & 6, drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
General Description		
<p>The lands of the Tp. are well set with rich bunch grass, affording extensive and excellent range for stock.</p> <p>There is water in the N.E. Cor. of the Tp., standing in holes during the dry season, but with little labor, could</p>		