

Exterior Lines of T. 4 N., R. 32 E., W.M. (N. Bdy.)

Chains		Feet
80.00	Set post Standard Cor. for Secs. 34 & 35; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass Soil; 2nd rate.	0
E. on S. Bdy. of Sec. 35, T 5 N., R. 32 E., Var. 20° E.		
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Standard Cor. for Secs. 35 & 36; land slopes to the S. Drove charred stake, dug pits and raised mound as per instructions. This line passes over rolling land, good grass Soil; 2nd rate.	
E. on S. Bdy. of Sec. 36, T. 5 N., R. 32 E. Var. 20° E.		
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits as per instructions.	
80.00	Set post Standard Cor. for Tp. 5 N., in Rgs. 32 & 33 E. Drove charred stake, dug pits and raised mound as per instructions. Land; gently rolling, good grass Soil; good 2nd rate.	
Exterior Bdy. of T. 4 N., R. 32 E., W.M. (E. Bdy.) As surveyed by Wm. H. O'NEILL & Wm. S. Lewis, U.S. Deputy Surveyors. Under Contract No. 110 Dated Feb. 7th, 1865		
Commenced the survey of the Exterior lines of T. No. 4 N., R. 32 E. of W.M. April 29th, 1865.		
N. on E. Bdy. of Sec. 36, T 4 N., R. 32 E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 25, 36, 30 & 31; drove charred stake dug pits and raised mound as per instructions.	