

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	stake, dug pits & raised mound as per instructions.	
79.24	To post Cor. Land; gently rolling Grass Good Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 25 & 26, T 4 N., R. 32 E. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post, on side of hill sloping to the N., drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 23, 24, 25 & 26, on hill sloping gently to the E.; drove charred stake, dug pits & raised mound as per instructions. Land; gently rolling Grass good Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 24 & 25, T 4 N., R. 32 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.53	Intersect N. & S. Tp. line, 45 lks. N. of post, from which I run N. 89° 41' W. on true line	
39.76	Set $\frac{1}{4}$ Sec. post in flat, drove charred stake, dug pits & raised mound as per instructions.	
79.53	To post Cor. Land; gently rolling Grass good Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 23 & 24, T. 4 N., R. 32 E. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
59.00	Gulch in which is standing water, course of gulch, S. 30° W.	