

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 3 & 10, T 4 N R 32 E	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect N. & S. line, 20 lks. N. of post, from which I run	
	W. $89^{\circ} 51'$ W. on true line	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	To post Cor.	
	Land; rolling, grass good	
	Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 3 & 4, T 4 N R 32 E	
		Var. $20^{\circ} 30'$ E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
71.50	Intersect 1st Standard Parallel, 20 lks. E. of post Cor. for Secs. 33 & 34. Set Closing Cor. post for Secs. 3 & 4, drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, grass good	
	Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 32 & 33, T 4 N R 32 E	
		Var. $20^{\circ} 15'$ E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 28, 29, 32 & 33; drove charred stake, dug pits and raised mound as per instructions.	
	Land; rolling, grass good	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 28 & 33, T 4 N R 32 E	
40.00	Set temp. $\frac{1}{4}$ Sec. post	