

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

| Chains | | Feet |
|--|---|------|
| 80.00 | Set post Cor. for Secs. 16, 17, 20 & 21, on side hill sloping N.; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass good Soil; 2nd rate. | |
| E. on random bet. Secs. 16 & 21, T 4 N., R 32 E. | | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post | |
| 79.15 | Intersect N. & S. line, 50 lks. N. of post, from which I run N. $89^{\circ} 53'$ W. on true line | |
| 39.57 | Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions. | |
| 79.15 | To post Cor. Land; rolling, grass good Soil; 2nd rate. | |
| N. on random bet. Secs. 9 & 16, T 4 N R 32 E | | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post | |
| 80.00 | Intersect N. & S. line, 40 lks. N. of post from which I run N. $89^{\circ} 43'$ W. on true line | |
| 40.00 | Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions. | |
| 80.00 | To post Cor. Land; rolling, grass good Soil; 2nd rate. | |
| N. bet. Secs. 8 & 9, T 4 N R 32 E | | |
| 40.00 | Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions. Var. $20^{\circ} 30'$ E | |
| 80.00 | Set post Cor. for Secs. 4, 5, 8 & 9; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass, good Soil; 2nd rate. | |