

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	E. on random bet. Secs. 4 & 9, T 4 N R 32 E	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.30	Intersect N. & S. line, 10 lks. S. of post, from which I run	
	S. $89^{\circ} 55'$ W. on true line	
40.15	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.30	To post Cor. Land; broken, grass good Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 4 & 5, T 4 N R 32 E	
		Var. $20^{\circ} 30'$ E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
71.75	Intersect First Standard Parallel, 10 lks. E. of post, for Secs. 32 & 33, T 5 N R 32 E. Set Closing Cor. post in Secs. 4 & 5, drove charred stake, dug pits & raised mound as per instructions. Land; broken Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 31 & 32, T 4 N R 32 E	
		Var. $20^{\circ} 30'$ E
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set Post Cor. for Secs. 29, 30, 31 & 32; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass good Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 29 & 32, T 4 N R 32 E	
40.00	Set temp. post	May 5, 1865.
79.10	Intersect N. and S. line, 15 lks. S. of post, from which I run S. $89^{\circ} 54'$ W. on true line.	