

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
39.55	Set $\frac{1}{4}$ Sec. post; dug pits, drove charred stake, and raised mound as per instructions.	
79.10	To post Cor. Land; rolling, grass good Soil; 2nd rate.	
<hr/> W. on random bet. Secs. 30 & 31, T 4 N R 32 E		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.70	Intersect N. & S. T _{p.} line, 90 lks. S. of post, from which I run	
40.70	S. $89^{\circ} 30'$ E. on true line	
40.70	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.70	To Post Cor. Land; rolling, grass good Soil; 2nd rate.	
<hr/> N. bet. Secs. 29 & 30, T 4 N R 32 E.		
40.00	Set $\frac{1}{4}$ Sec. post in bottom of small hollow; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 19, 20, 29 & 30, on top of hill in a small sag; hill sloping to S. Drove charred stake dug pits and raised mound as per instructions. Land; rolling, grass good Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 20 & 29, T 4 N R 32 E		
40.00	Set temp. post	
79.75	Intersect N. & S. line, 53 lks. N. of post, from which I run N. $89^{\circ} 37'$ W. on true line.	
39.87	Set $\frac{1}{4}$ Sec. post on W. side of ravine, drove charred stake, dug pits and raised mound as per instructions.	
79.75	To post Cor. Land; rolling	