

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	Grass; good Soil; 2nd rate.	
<hr/>		
	W. bet. Secs. 19 & 30, T 4 N R 32 E	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.50	Intersect N. & S. Tp. line, 50 lks. N. of post from which I run	
	N. 89° 38' E. on true line	
39.50	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions	
79.50	To post Cor.	
	Land; rolling Grass good Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 19 & 20, T 4 N R 32 E	
	Var. 21° E	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions	
80.00	Set post Cor. for Secs. 17, 18, 19 & 20, on top of hill, gently sloping to the S.W.; drove charred stake, drove charred stake, dug pits and raised mound as per instruc- tions.	
	Land; rolling Grass good Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 17 & 20, T 4 N R 32 E	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.50	Intersect N. & S. line, 62 lks. S. of post from which I run	
	S. 89° 33' W. on true line	
39.75	Set $\frac{1}{4}$ Sec. post on side of ravine, sloping to the W.; drove charred stake, dug pits and raised mound as per instructions.	