

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
40.20	Set $\frac{1}{4}$ Sec. post on land sloping a little to the W. Drove charred stake, dug pits and raised mound as per instructions.	
80.40	To post cor. Land; gently rolling, good grass. Soil; good 2nd rate.	
<hr/> N. bet. Secs. 25 & 26, T. 4 N R 33 E.		
Var. 21° E.		
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post Cor. for secs. 23, 24, 25 & 26, drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass. Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 24 & 25, T. 4 N R.33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
56.85	Trail, course N.W.	
80.25	Intersect N. and S. line 15 lks. S. of post, from which I run S. 89° 54' W. on true line	
40.00	Set $\frac{1}{4}$ Sec. post on level. Drove charred stake, dug pits and raised mound as per instructions.	
80.25	To post Cor: Land; rolling, grass good Soil; 2nd rate.	
<hr/> N. bet. Secs. 23 & 24, T. 4 N., R. 33 E.,		
Var. 21° E.		
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post Cor. for Secs 13, 14, 23 & 24. Drove charred stake dug pits and raised mound as per instructions. Land; rolling, grass good	