

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
79.15	To post Cor. Land; broken, good grass. Soil; 2nd rate.	
<hr/> N. bet. Secs. 20 & 21, T. 4 N., R. 33 E., Var. 21° E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for secs. 16, 17, 20 & 21; drove charred stake, dug pits and raised mound as per instructions. Land; broken grass good Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 16 & 21, T. 4 N., R. 33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.25	Intersect N. and S. line, 58 lks. N. of post, from which I run N. 89° 35' W. on true line	
39.62	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
79.25	To post cor. Land; rolling, grass good. Soil; 2nd rate.	
<hr/> N. bet. Secs. 16 & 17, T. 4 N., R. 33 E. Var. 21° E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post cor. for Secs. 8, 9, 16 & 17; drove charred stake, dug pits and raised mound as per instructions. Land; broken Soil; 2nd rate. Grass; good.	
<hr/> E. on random bet. Secs. 9 & 16, T. 4 N., R. 33 E.		