

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
	E. on random bet. Secs. 20 & 29, T. 4 N., R. 33 E. Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.15	Intersect N. and S. line at post from which I run W. on a true line	
39.57	Set $\frac{1}{4}$ Sec. post; dug pits, drove charred stake & raised mound as per instructions.	
79.15	To post cor. Land; broken, grass good Soil; 2nd rate.	
<hr/> N. bet. Secs. 19 & 20, T. 4 N., R. 33 E.		
	Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for secs. 17, 18, 19 & 20; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass good. Soil; 2nd rate.	
<hr/> May 1st. 1865		
	E. on random bet. Secs. 17 & 20, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.00	Intersect N. and S. line, 35 lks. N. of post from which I run N. 89° 45' W. on true line	
39.10	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
79.00	To Post Cor. Land; rolling, grass good. Soil; 2nd rate.	
<hr/> N. bet. Secs. 17 & 18, T. 4 N., R. 33 E.		
	Var. 21° E.	
40.00	Set $\frac{1}{4}$ sec. post; drove charred stake, dug pits and raised mound as per instructions.	