

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
	N. bet. Secs. 6 & 5, T. 4 N., R. 33 E.	
	Var. 20° E.	
40.00	Set $\frac{1}{4}$ Sec. post cor.; drove charred stake, dug pits and raised mound as per instructions.	
71.20	Intersect 1st Standard Parallel N. 6.80 chs. W. of Stand. Cor. for secs. 31. 32, T. 5 N., R. 33 E. Set C. Cor. for secs. 5 & 6, drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, grass good	
	Soil; 2nd rate.	
<hr/>		
	W. on random bet. Secs. 30 & 31, T. 4 N., R. 33 E.	
41.10	Set temp. $\frac{1}{4}$ Sec. post cor.	
75.85	Intersect W. Tp. line, 60 lks. S. of post from which I run	
	S. 89° 34' E. on true line	
35.85	Set $\frac{1}{2}$ sec. post; drove charred stake, dug pits and raised mound as per instructions.	
75.85	To post cor.	
	Land; rolling, good grass.	
	Soil; 2nd rate.	
<hr/>		
	W. on random bet. Secs. 19 & 30, T. 4 N., R. 33 E.	
40.00	Set $\frac{1}{4}$ Sec. temp. cor.	
75.70	Intersect W. Tp. line, 59 lks. S. of post from which I run S. 89° 35' E. on true line	
35.70	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
75.70	To post cor.	
	Land; rolling, grass good	
	Soil; 2nd rate.	
May 5, 1865.		
<hr/>		
	W. on random bet. Secs. 18 & 19, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
75.92	Intersect N. and S. Tp. line, 58 lks. S. of post. from which I run	