

## Exterior Bdy. of T. 4 N., R. 34 E., W.M. (E. Bdy.)

Chains		Feet
	stake, dug pits and raised mound as per instructions. Land; on S. $\frac{1}{2}$ level, N. $\frac{1}{2}$ gently rolling, good grass. Soil; good 2nd rate.	
	N. on E. Bdy. of Sec. 12 <div style="text-align: right;">Var. 20° 30' E.</div>	
40.00	Set $\frac{1}{4}$ Sec. post cor.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post cor. for secs. 1, 12, 6 & 7; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass. Soil; good 2nd rate.	
	N. on E. Bdy. of Sec. 1 <div style="text-align: right;">Var. 20° 30' E.</div>	
40.00	Set $\frac{1}{4}$ sec. post cor.; drove charred stake, dug pits and raised mound as per instructions.	
69.60	Intersect 1st Standard Parallel N., 5.78 Chs. W. of Post Cor. for T. 5 N., R. 34 & 35 E. Set Closing Cor. for T. 4 N., R. 34 & 35 E., Secs. 1 & 6; drove charred stake, dug pits and raised mound as per instructions. Land; rolling prairie, good grass. Soil; 2nd rate.	
	W. Bdy. T. 4 N. R. 35 E., W.M. As surveyed by Z.F. Moody, U.S. Deputy Surveyor Under Contract No. 165, Dated Oct. 4, 1871.	
	Begin at the cor. to tps. 3 & 4 N., Rs 34 & 35 E. I run N. on W. Bdy. of Sec. 31	
40.00	Set post for $\frac{1}{4}$ Sec. and made mound of earth	
80.00	Set post and made earth mound for cor. Secs. 31, 36, 25 & 30. Land; rolling Soil; good, good grass.	