

## Exterior Bdy. of T. 3 N., R. 35 E., W.M.

Chains		Feet
	<p>2 notches on S. and 4 notches on N. edges, raised a mound of earth, 2 ft. high, <math>4\frac{1}{2}</math> ft. base around post.</p> <p>Land; level</p> <p>Soil; 1st rate.</p> <p>Good grass.</p>	
	S. on E. Bdy. Sec. 25	
		Var. 20° E.
1.35	Leave field	
40.00	<p>Deposited a charred stake, 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. Cor., dug pits, 18 x 18 x 12 ins. N. &amp; S. of Cor., <math>5\frac{1}{2}</math> ft. dist., and raised a mound of earth, <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it; intersect pit, drove a stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked <math>\frac{1}{4}</math> on W. face.</p>	
54.00	Dry ditch, course N.W.	
60.00	Enter field	
80.00	<p>Set a post, 48 x 4 x 4 ins., 12 ins. in the ground for Cor. to Secs. 30, 31, 25 &amp; 36, marked R. 35 E., S. 30 on N.E., S. 31 on S.E., R. 34 E., S. 36 on SW., T. 4 N. S. 25 on NW. faces, with 5 notches on N., and 1 notch on S. edges. Dug pits, 18 x 18 x 12 ins., in each Sec. <math>5\frac{1}{2}</math> ft. dist., raised a mound of earth, 2 ft. high, <math>4\frac{1}{2}</math> ft. base around post.</p> <p>Land; level, some grass.</p> <p>Soil; 1st rate.</p>	
	S. on E. Bdy. Sec. 36	
		Var. 19° 45' E.
12.45	Leave field	
20.00	<p>Deposited charred stake, 12 ins. in the ground for <math>\frac{1}{16}</math> Sec. Cor.; dug pits, 18 x 18 x 12 ins. N. &amp; S. of Cor. <math>\frac{E}{2} + \frac{W}{2}</math> <math>5\frac{1}{2}</math> ft. dist., raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it. In E. pit, drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked <math>\frac{1}{16}</math> Sec. on W. face.</p>	
24.25	Wagon Road, course N.W. & S.E.	