

## Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	Soil; good 2nd rate.	
	E. on random bet. Secs. 25 & 36 Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. post	
80.23	Intersect N. and S. line, 12 lks. N. of Post Cor. S. 89° 54' W. on true line	
40.11	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.23	To post Cor. Land; gently rolling, good grass. Soil; good 2nd rate.	
	N. bet. Secs. 25 & 26 Var. 21° E.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
52.85	Wild Horse Creek, 10 lks. wide, course S.W., and enter field.	
80.00	Set post Cor. for Sec. 23, 24, 25 & 26; drove charred stake dug pits and raised mound as per instructions. Land; gently rolling. Soil; 1st rate.	
	E. on random bet. Secs. 24 & 25 Var. 20° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.40	Intersect N. & S. line, 26 lks. N. of post Cor. S. 89° 49' W. on true line	
40.20	Set true Cor.; drove charred stake, dug pits and raised mound as per instructions.	
45.00	Wild Horse Creek, 10 lks. wide, course S.W.	
45.50	Enter field	
80.40	To post Cor. Land; gently rolling Soil; 1st rate. July 31st, 1866.	
	N. bet. Secs. 23 & 24	
11.50	Leave field.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits, raised mound as per instructions.	