

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	stake, dug pits and raised mound as per instructions. Land; broken, grass excellent Soil; 2nd rate.	
E. on random bet. Secs. 22 & 27		
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.	
79.84	Intersect N. and S. line, 34 lks. N. of post cor. N. 89° 45' W. on true line	
39.92	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.84	To post cor. Land; broken, grass good. Soil; 2nd rate.	
N. bet. secs. 21 & 22		
40.00	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post cor. for secs. 15, 16, 21 & 22; drove charred stake, dug pits, and raised mound as per instructions.	
80.00	Set post cor. for secs. 15, 16, 21 & 22; drove charred stake, dug pits, and raised mound as per instructions. Land; rolling, good grass. Soil; 2nd rate.	
E. on random bet. Secs. 15 & 22		
		Var. 21° E.
40.00	Set post cor. for $\frac{1}{4}$ Sec. temp.	
79.77	Intersect N. and S. line, 54 lks. N. of post cor. N. 89° 37' W. on true line	
39.88	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.77	To post cor. Land; broken good grass Soil; 2nd rate.	