

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	2 ft. high, $4\frac{1}{2}$ ft. base around it	
47.30	Dry ditch on old channel of Wild Horse Creek, S.W.	
50.00	Wild Horse Creek, 10 lks. wide, S.W.	
80.64	Cor. to Secs. 23, 24, 25 & 26	
	Land; level	
	Soil; 1st rate.	
	No timber, mostly cultivated	
	<hr/>	
	S. bet. Secs. 25 & 26	
		Var. $18\frac{1}{2}^{\circ}$ E.
27.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in the ground for Witness Meander Cor. to fractional Secs. 25 and 26, marked W. R. M.C.W.C. with T. 4 N. on N., R. 34 E. S. 25 on E. and S. 26 on W. faces and dug a pit, 3 ft. sq. 1 ft. deep, 8 lks. N. of post, which is 20 lks. N. of true Cor. and raised mound of earth, 2 ft. high, $4\frac{1}{2}$ ft. base around it	
27.20	Middle of Wild Horse Creek, 10 lks wide, runs S.W.	
35.25	Leave field, course E. and W.	
37.50	O.R. & N., R.R. course S.W.	
40.00	Set post, 4 ft. long, 4 in. sq., 24 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face; dug pits, 18 x 18 x 12 ins. N. and S. of post, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.	
80.00	Set post, 4 ft. long 4 ins. sq. 24 ins. in the ground for Cor. to Secs. 25, 26, 35 & 36, marked, T. 4 N. S. 25 on N.E., R. 34 E., S. 36 on S.E., S. 35 on S.W. and S. 26 on NW. faces, with 1 notch on S. and E. edges, and raised mound of stone, 2 ft. high, $4\frac{1}{2}$ ft. base around post.	
	Land; mostly level	
	Soil; rich bottom, sandy, mostly cultivated.	
	<hr/>	
	E. on random bet. Secs. 25 & 36	
		Var. $19\frac{3}{4}^{\circ}$ E.
	Set temp. $\frac{1}{4}$ and $1/16$ Sec. Cor., at 20, 40 and 60 chs. and	