

1.

Exterior Bdy. of T. 5 N. R. 34 E., W.M.  
 As surveyed by Wm. H. Odell & Wm. S. Lewis, U.S. Deputy Surveyors  
 Under Contract No. 110  
 Dated Feb. 7, 1865

Chains		Feet
	E. on S. Bdy. of Sec. 31, T 35 E., No. 5 N.  Var. 20° E.	
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec.; land slopes to the E.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set Standard Cor. for Secs. 31 & 32, on hill slopes to the E., from which  A Pine 20 ins. in diam. brs. S. 88° E., 5.25 lks. A Balm, 10 ins in diam. brs. N. 60° E., 313 lks.  The pine stands on opposite side of Pine Creek in edge of water, bank to steep and the water to deep to put the proper markes on the Pine, dug pits and made mound as per instructions.  Land; quite broken  Good grass  Soil; 2nd rate.	
<hr/>		
	E. on S. Bdy. of Sec. 32, T 5 N R 35 E  Var. 20° E.	
5.00	Pine Creek, 25 lks. wide, course N. Some scattering timber along Creek	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and made mound as per instructions	
80.00	Set post Standard Cor. for Secs. 32 & 33 on level; drove charred stake, dug pits and raised mound as per instruc- tions.  Land; on las half mile, gently rolling, good grass  Soil; good 2nd rate.	
<hr/>		
	E. on S. Bdy. of Sec. 33, T 5 N R 35 E.  Var. 20° E.	
40.00	Set Standard Cor. for $\frac{1}{4}$ Sec. on level; drove charred stake, dug pits and raised mound as per instructions.	
59.00	Stage Road from Walla Walla to Grand Rounde, course, N.E. & S.W.	
80.00	Set post Cor. for Secs. 33 & 34 on level; drove charred	