

Exterior Bdy. of T 5 N R 35 E., W.M. (E. Bdy.)

Chains		Feet
70.00	Summit of ridge	
80.00	Set post Cor. for Secs. 13 & 24, 18 & 19, in ravin, course N.W.; drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
<hr/> N. on E. Bdy. of Sec. 13		
Var. 21° E.		
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on W. side of hill; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 12, 13, 7 & 18, on land sloping to the N.; drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass excellent Soil; 2nd rate.	
<hr/> N. on E. Bdy. of Sec. 12		
Var. 21° E.		
32.80	Enter field, course of fence N.W. and S.E.	
41.00	Set post Cor. for $\frac{1}{4}$ Sec. from which A Balm, 5 ins. diam. brs. S. 50° E. 65 lks. A " 20 " " " N. 80° W. 4.31 lks.	
45.00	Dry Creek, channel dry, course N.W.	
47.00	Leave field	
80.00	Set post Cor. for Secs. 1, 12, 6 & 7, hill sloping to the W.; drove charred stake, dug pits and raised mound as per instructions. Land; broken Grass excellent Soil; in field, 1st rate, on hill side, 2nd rate.	
<hr/> N. on E. Bdy. of Sec. 1		
Var. 20° E.		
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on land sloping to the E.; drove charred stake, dug pits and raised mound as per instructions.	