

Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
80.33	Intersected N. & S. line, 25 lks. S. of post Cor. S. 89° 49' W. on true line	
16.75	Spring branch, 3 lks. wide, course N.W.	
40.16	Set post Cor. for $\frac{1}{4}$ Sec. on hillside facing the N.; drove charred stake, dug pits and raised mound as per instructions.	
59.00	Small spring branch, 2 lks. wide, course N.	
80.33	To post Cor. Land; broken, good grass Soil; 2nd rate.	
<hr/> N. bet. Secs. 13 & 14		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
62.25	Spring branch, 5 lks. wide, course N.W.	
78.42	" " 1 " " " W.	
80.00	Set post Cor. for Secs. 11, 12, 13 & 14, on hillside, facing the W.; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 12 & 13		
Var. 21° E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.18	Intersected N. & S. line, 41 lks. S. of post S. 89° 42' W. on true line	
40.09	Set $\frac{1}{4}$ Sec. post Cor. on hillside facing the S.; drove charred stake, dug pits and raised mound as per instructions.	
80.18	To post Cor. Land; broken, good grass Soil; 2nd rate.	
August, 18th, 1866.		