

Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
	drove charred stake, dug pits and raised mound as per instructions	
80.00	Set post Cor. for Secs. 26, 27, 34 & 35, drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 26 & 35	
		Var. 19° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.87	Intersected N. & S. line, 28 lks. S. of Post Cor. S. 89° 48' W. on true line	
39.93	Set basalt stone, 8 x 12 x 16, Cor. for $\frac{1}{4}$ Sec., on hillside facing the W.	
65.90	Road, course N.W.	
66.20	Enter field, course of fence, N.W. & S.E.	
71.12	Leave field, course of fence, N.E. & S.W.	
72.50	Pine Creek, course N.W. channel dry.	
79.87	To post Cor. Land; broken, grass good Soil; in field 1st rate, on hillside	
<hr/>		
	N. bet. Secs. 26 & 27	
8.25	Pine Creek, course N.W., channel dry	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 22, 23, 26 & 27; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; good 2nd rate.	
<hr/>		
	E. on random bet. Secs. 23 & 26	
		Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.74	Intersected N. & S. line, 37 lks. S. of post Cor. S. 89° 44' W. on true line	