

## Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
39.87	Set post Cor. for $\frac{1}{4}$ Sec. on W. slope of hill; drove charred stake, dug pits and raised mound as per instructions.	
79.74	To post Cor. Land; broken, good grass Soil; good 2nd rate. Mr. Lewellen has settled upon the N.W. $\frac{1}{4}$ of Sec. 26, and has about 20 acres under cultivation.	
N. bet. Secs. 22 & 23		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 14, 15, 22 & 23; drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass good Soil; good 2nd rate.	
August 20th, 1866.		
E. on random bet. Secs. 14 & 23		
Var. $21^{\circ}$ E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.82	Intersected N. & S. line, 23 lks. S. of post Cor. S. $89^{\circ} 50'$ W. on true line	
39.91	Set post Cor. for $\frac{1}{4}$ Sec.; on land that slopes to the N.W.; drove charred stake, dug pits and raised mound as per instructions.	
68.00	Enter field, course of fence, N.W. and S.E.	
74.00	Small spring branch, course N.W. and leave field	
79.82	To post Cor. Land; broken, grass good Soil; good 2nd rate.	
N. bet. Secs. 14 & 15		
13.25	Boise City and Walla Walla stage road, course, N.E. & S.W.	
18.55	Enter field, course of fence, N.E. & S.W.	
30.00	Leave field, course of fence, N.W. & S.E.	
40.00	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits and	