

Subdivisional Lines of T 4 N R 35 E., W.M.

Chains		Feet
	raised mound as per instructions.	
80.00	Set post Cor. for Secs. 10, 11, 14 & 15; drove charred stake, dug pits and raised mound as per instructions. Land; gently rolling, good grass Soil; good 2nd rate.	
<hr/>		
	E. on random bet. Secs. 11 & 14	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.92	Intersected N. & S. line, 47 lks. S. of post Cor. S. 89° 40' W. on true line	
10.21	W. branch of Dry Creek, 3 lks. wide,	
39.96	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
42.00	Boise City and Walla Walla Stage Road, course N.	
79.92	To post Cor. Land; rolling, good grass Soil; good 2nd rate.	
<hr/>		
	N. bet. Secs. 10 & 11	
40.00	Set post Cor. for $\frac{1}{4}$ Sec., on level; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 2, 3, 10 & 11, on level; drove charred stake, dug pits and raised mound as per instructions. Land; gently rolling, grass excellent Soil; good 2nd rate.	
<hr/>		
	E. on random bet. Secs. 2 & 11	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.87	Intersected N. & S. line, 10 lks. N of post Cor. N. 89° 56' W. on true line	
33.67	W. branch of Dry Creek, 4 lks. wide, course N.	
36.80	Boise City and Walla Walla Stage Road, course N.	