

Subdivisional Lines of T. 4 N., R. 35 E. W.M.

Chains		Feet
60.00	Boise City and Walla Walla Stage Road, course N.E. & S.W.	
80.15	To post Cor. Land; rolling, good grass Soil; good 2nd rate.	
N. bet. Secs. 27 & 28		
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on gentle slope to the N.E.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 21, 22, 27 & 28, on land slopes to the E.; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass Soil; good 2nd rate.	
E. on random bet. Secs. 22 & 27		
Var. 21° E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.10	Intersect N. & S. line, 15 lks. S. of Post Cor. S. 89° 56' W. on true line	
30.00	Top of steep Bluff on Pine Creek, forming on side of field	
33.75	Pine Creek, 8 lks. wide, course N.	
37.55	Leave field and cross Boise City and Walla Walla Stage Road, course N.	
39.55	Enter House	
39.90	Leave House	
40.05	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions. N.W. Cor. of Stone Chimney, brs. E., 15 lks.	
80.10	To post Cor. Land; broken, good grass Soil; good 2nd rate.	
N. bet. Secs. 21 & 22		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits	