

## Resurvey of Subdivisional Lines of T. 4 N R 35 E., W.M.

Chains		Feet
35.60	Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face, dug pits, 18 x 18 x 12 ins. E. & W. of post $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.	
49.10	House about 24 ft x 16 ft., one story	
55.10	Fence, N. & S.	
56.00	Wagon road, N. & S.	
56.37	E. bank of Wild Horse Creek, 10 lks. wide, and at	
57.37	Set post 4 ft. long, 4 ins. sq., 24 ins. in the ground for Meander Cor. to fractional Sec. 19 & 30, marked U.R.M.C. with T 4 N on W., R. 35 E., S. 19 on N. & S. 30 on S. faces & dug a pit, 3 ft. sq., 1 ft. deep, 8 lks. W. of post and raised mound of earth, 2 ft. high, $4\frac{1}{2}$ ft. base around it	
75.60	Cor. to Secs. 19, 20, 29 & 30 Land; level Soil; 1st rate. All cultivated.	
	S. bet. Secs. 29 & 30 Var. 21° E.	
25.00	Enter orchard, E. & W.	
30.00	S. bank of Wild Horse Creek, 10 lks. wide and set basalt stone, 10 x 10 x 10 ins. 7 ins. in the ground for Meanders to fractional Secs. 29 & 30, marked U.R.M.C. on S. face and dug a pit, 3 ft. sq., 1 ft. deep, 8 lks. S. of stone and raised mound of earth, 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
37.25	Fence and enter field	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground marked $\frac{1}{4}$ S. on W. face, dug pits, 8 x 18 x 12 ins., N & S. of post $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.	
80.00	Set post 4 ft. long, 4 ins. sq., 24 ins. in the ground for Cor. to Secs. 29, 30, 31 & 32, marked	