

Resurvey of Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
	S. on true line bet. Secs. 31 & 32 Var. 20° E.	
20.00	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. cor. dug pits, 18 x 18 x 12 ins. N. & S. of stake, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base over it and in N. pit; drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S. on W. face.	
20.50	Fence & field, E. & W.	
40.00	Deposited charred stake, 12 ins. in the ground for ¼ Sec. Cor., dug pits, 18 x 18 x 12 ins., N. & S. of stake, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in N. pit; drove stake 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked ¼ S. on W. face.	
60.00	Deposited charred stake, 12 ins. in the ground for ¼ Sec. Cor., dug pits, 18 x 18 x 12 ins. N. & S. of stake, 5½ ft., raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in N. pit; drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S. on W. face.	
79.20	Intersect S. Bdy. of Tp. 123 lks. W. of Cor. to Secs. 5 & 6, T 3 N R 35 E. and set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for closing Cor. to Secs. 31 & 32, marked C.C. T 4 N on N., R 35 E S 32 on E. & S 31 on W. faces, with 5 notches on E. and 1 notch on W. edges, dug pits, 18 x 18 x 12 ins. N.E. & W. of Cor. 5½ ft. dist., raised mound of earth, 2 ft. high, 4½ ft. base around it.	
	Land; mostly level Soil; 1st rate, partly cultivated.	
	Commencing at Cor. to Secs. 28, 29, 32 & 33, which is charred stake, 12 ins. in the ground and pits in each sec. 5½ ft. dist., almost obliterated, I run	
	S. on true line bet. Secs. 32 & 33 Var. 21° E.	