

## Sub-subdivisions of T 4 N., R. 35 E., W.M. (Sec.

Chains		Feet
	face.	
35.90	Deposited charred stake, 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor.; dug pits 18 x 18 x 12 in E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked: $\frac{1}{4}$ S. on N. face.	
55.90	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor., dug pits 18 x 18 x 12 ins. E. & W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit; drove stake, 2 ft. long 2 ins. sq., 12 ins. with ground, marked: 1/16 S. on N. face.	
75.90	To point of beginning Land; rolling slightly Soil; 1st rate.	
W. on random through N. $\frac{1}{2}$ of Sec. 31 Var. 20° E. Commencing at 1/16 Sec. Cor., 20 chs. N. of $\frac{1}{4}$ Sec. Cor. bet. Secs. 31 & 32. Set temp. Cor. at 20, 40 & 60 Chs. and at		
75.70	Intersect W. Bdy. of Tp., 36 lks. S. of 1/16 Sec. Cor., thence S. 89° 45' E. on true line	
15.00	Fence and enter field, N. & S.	
15.70	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor., dug pits 18 x 18 x 12 ins. E. & W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit; drove stake 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked: 1/16 S. on N. face.	
35.70	Deposited charred stake, 12 ins. in the ground for 1/16 sec. Cor., dug pits 18 x 18 x 12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist., raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit; drove stake, 2 ft. long,	