

Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
	N. 89° 43' W. on true line	
39.82	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, and raised stone mound as per instructions.	
61.00	Bottom of ravine, course N.	
79.65	To post Cor. Land; broken, good grass Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 15 & 16	
10.00	Bottom of ravine, course N.E.	
40.00	Set basalt stone, 5 x 11 x 15, cor. for $\frac{1}{4}$ Sec. on point of ridge, course N.E.	
66.50	Dry creek, channel dry, course W.	
80.00	Set post Cor. for Secs. 9, 10, 15 & 16; drove charred stake, and raised stone mound as per instructions. Land; broken, good grass Soil; stony.	
<hr/>		
	E. on random bet. Secs. 10 & 15 Var. 19° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.71	Intersected N. and S. line, 57 lks. N. of post Cor. N. 89° 36' W. on true line	
39.80	Set basalt stone, 8 x 10 x 15, cor for $\frac{1}{4}$ Sec., on hill-side facing the S.	
79.71	To post Cor. Land; broken, good grass Soil; rocky.	
<hr/>		
	N. bet. Secs. 9 & 10	
15.00	Road, course E. and W.	
40.00	Set basalt stone, 9 x 10 x 12 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post Cor. for Secs. 3, 4, 9 & 10; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass,	

Oct. 5th, 1866.