

Subdivisional Lines of T 4 N R 36 E., W.M.

Chains		Feet
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 3 & 10	
		Var. 20° 30' E.
40.00	Made temp. $\frac{1}{4}$ Sec. Cor.	
79.67	Intersected N. and S. line, 63 lks. N. of post Cor.	
	N. 89° 33' W. on true line	
36.00	Bottom of ravine, course N.	
39.83	Set post Cor. for $\frac{1}{4}$ Sec. on side hill facing the N.E.; drove charred stake, dug pits and raised mound as per instructions.	
60.00	Summit of ridge, course N.	
77.50	Bottom of ravine, course N.	
79.67	To post Cor.	
	Land; very broken	
	Good grass	
	Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 3 & 4	
15.75	Creek, 5 lks. wide, course W.	
40.00	Set basalt stone, 6 x 12 x 14 for $\frac{1}{4}$ Sec. Cor.	
68.23	Intersected the 1st Standard Parallel N., 12.30 W. of post Cor. for Secs. 33 & 34, T 5 N R 36 E. Set post Closing Cor. for Secs. 3 & 4; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
		October 5th, 1866.
	<hr/>	
	N. bet. Secs. 32 & 33	
22.50	Pine Creek channel dry, course W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, and raised stone mound as per instructions.	
80.00	Set post Cor. for Secs. 28, 29, 32 & 33, in prairie, drove charred stake, dug pits and raised mound as per instruc- tions.	