

Exterior Bdy. of T 4 N R 37 E., W.M. (N.Bdy.)  
 As surveyed by Wm. H. Odell, U.S. Deputy Surveyor  
 Under Contract No. 110,  
 Dated Feb. 7th, 1865.

Chains		Feet
	E. on S. Bdy. of Sec. 31. T 5 N R 37 E. Var. 23° 50' E.	
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec. on side of ravine, ground sloping to the N.W.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Made Standard Cor. for Secs. 31, 32 on Pine Tree, 60 lks. E. of true Cor., Pine, 18 ins. diam. standing on hillside very steep.	
<hr/> Finding it impractaoble to proceed further on line I run, N. 11° E. 9.65, thence S. 62° 30' E. 20.00 making distance on line from true cor. 20.60, thence W. to river, 13.50 to Walla Walla River, 75 lks. wide, Course N.W.		
30.00	Saw Mill, brs. S. about 20.00	
40.00	Made standard cor. for $\frac{1}{4}$ Sec. on perpendicular basalt rock, 50 lks. W. of true Cor., hillside too steep to make permanent Cor. by planting post.	
53.00	Summit of ridge, course S.W.	
76.00	Bottom of ravine	
80.00	Set Standard Cor. for Secs. 32 & 33, on steep hillside, facing N.W. T 5 N R 37 E.; drove charred stake, dug pits and raised mound as per instructions. Land; very broken hillsides. Rocky, grass 2nd rate.	
	<hr/> E. on S. Bdy. of Sec. 33, T 5 N R 37 E Var. 21° E.	
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec.; drove charred stake dug pits and raised mound as per instructions.	
57.00	Summit of divide, course N.W.	
80.00	Set Standard Cor. for Secs. 33 & 34, on side hill facing NE.; drove charred post, dug pits and raised mound as per instructions.	