

Exterior Bdy. of T 4 N R 37 E., W.M. (N. Bdy.)

Chains		Feet
80.00	<p>A Fir tree, 18 ins. in diam. S 75° E., 10 lks.</p> <p>Set Standard Cor. for Tp. 5 N. in Rs 37 & 38 & Secs. 36 and 31, from which</p> <p>A fir tree, 20 ins. in diam. N. 24°30' E., 19 lks.</p> <p>A fir Tree, 10 ins. in diam. S 6° 30' W. 80 lks.</p> <p>A fir tree, 8 ins. in diam. N. 73° W., 60 lks.</p> <p>This line passes through heavy timber, fir, pine & larch. Undergrowth; same and Vinemaple.</p> <p>Land; gently rolling.</p> <hr/> <p>Resurvey of N. Bdy. of T 4 N R 37 E., W.M. As surveyed by Geor. S. Pershin, U.S. Deputy Surveyor. Under Contract No. 332, Dated July 29, 1879.</p> <hr/> <p>* From cor. to Secs. 34 & 35 on 1st Standard Parallel N. I run W. on true line on the S. Bdy. of Sec. 34 Var. 20° 09' E.</p>	
6.50	Fence and field, course N.W. and S.E.	
22.50	Fence & leace field, course N.W. and S.E.	
40.00	Set Basalt stone, 16 x 12 x 8 on S. side of spur for $\frac{1}{4}$ Sec. cor.	
69.00	Gulch, course N.W.	
80.00	Set pine post in mound of stone on steep N.E. hillside for Cor. to Secs. 33 & 34.	
	*One witness tree to Cor. to secs. 34 & 35 is still standing.	
	viz: A fir, 24 ins. diam. brs. S. 44° E. 30 lks. dist. Surface on this mile is mountainous.	
	Note:- the part of this Tp. which I have ometted to survey is, in my judgment, not surveyable under present laws, not being agricultural nor timber lands of commercial value.	
	W. on true line on S. Bdy. of Sec. 33	
	Var. 20°30' E.	
40.00	Set basalt stone, 16 x 12 x 4 on S. hillside for $\frac{1}{4}$ Sec. Cor.	