

Subdivisional Lines of T 4 N., R 37 E., W.M.

| Chains |   | Feet |
|--------|---|------|
|        | <p>Yew and alder underbrush</p> <p>Timber much cut away in places.</p>  |      |
|        | <hr/>   |      |
|        | <p>W. on a random line bet. Secs. 28 &amp; 33</p> <p style="text-align: right;">Var. 21° E.</p>   |      |
| 40.00  | Set post for temp. $\frac{1}{4}$ Sec. Cor.  |      |
| 81.60  | <p>Intersected N. &amp; S. line, 390 lks. N. of Cor. to Secs. 28, 29, 32 &amp; 33, from which Cor. I run</p> <p>N. 87° 13' E. on a true line bet. Secs. 28 &amp; 33</p> <p style="text-align: right;">Var. 20° 00' E.</p>   |      |
| 31.50  | Spring branch, course N.W.  |      |
| 41.60  | <p>Set tamarack post on S.W. face of hill for <math>\frac{1}{4}</math> Sec. Cor.</p> <p style="padding-left: 40px;">A tamarack, 10 ins. diam. brs. N. 34° W., 34 lks. dist.</p> <p style="padding-left: 40px;">A tamarack, 8 ins. diam. brs. S. 50° E., 12 lks. dist.</p>   |      |
| 55.00  | Wagon road to Weston, N.W. and S.E.   |      |
| 81.60  | <p>The Cor. to Secs. 27, 28, 33 &amp; 34</p> <p>Land; surface rolling</p> <p>Soil; 3rd and 2nd rate.</p> <p>Heavy timber, but much of it cut away, tamarack, fir, spruce and hemlock.</p> <p>Yew and alder underbrush.</p>  |      |
|        | <hr/>   |      |
|        | <p>N. bet. Secs. 27 &amp; 28</p> <p style="text-align: right;">Var. 21° E.</p>  |      |
| 25.25  | Brook, 8 lks. wide, course N.W.   |      |
| 40.00  | <p>Set basalt stone, 16 x 10 x 4 ins. in mound of stone in small open glade on S. slope for <math>\frac{1}{4}</math> Sec. Cor.</p> <p style="padding-left: 40px;">A pine, 20 ins. diam. brs. N. 26° E., 107 lks. dist.</p> <p style="padding-left: 40px;">A fir, 8 ins. diam. brs. N. 74° W., 70 lks. dist.</p> <p style="padding-left: 40px;">A tamarack, 22 ins. diam. brs. S. 14° E., 63 lks. dist.</p>  |      |
| 80.00  | <p>Set fir post on N. descent for Cor. to Secs. 21, 22, 27 &amp; 28.</p> <p style="padding-left: 40px;">A fir, 8 ins. diam. brs. N. 34° E., 28 lks. dist.</p> <p style="padding-left: 40px;">A Tamarack, 22 ins. diam. brs. S. 14° E., 63 lks. dist.</p> <p style="padding-left: 40px;">A fir, 6 ins. diam. brs. S. 30° W., 36 lks. dist.</p> <p style="padding-left: 40px;">A fir, 15 ins. diam. brs. N. 28° W., 22 lks. dist.</p> <p>Land; surface broken</p> <p>Soil; 3rd rate.</p> <p>Heavy timber, fir, tamarack and spruce</p> <p>Yew and alder underbrush.</p> <p>Much timber cut.</p> |      |