

Subdivisional Lines of T 4 N R 37 E., W.M.

Chains		Feet
	<p>and at 3 miles, 1 ch. and 80 lks. intersected E. Bdy. 1186 lks. S. of Cor. to Secs. 1 & 12, making my correction, 62 lks. to the mile. I also divide the exception equal among the three miles, making each, 1 mile & 60 lks. I run S. 89° 33' W. on a true line bet. Secs. 1 & 12 Var. 22° 15' E.</p>	
7.00	Deep gulch	
40.30	<p>Set basalt stone, 16 x 4 x 4 on S. brow of bluff for ¼ Sec. Cor. A Pine, 15 ins. diam. brs. N. 42° W., 201 lks. dist. No tree on S. side.</p>	
52.00	Enter timber, N.E. and S.W.	
80.60	<p>Set fir post on S.W. slope of bluff for Cor. to Secs. 1, 2, 11 & 12. A Pine, 28 ins. diam. brs. N. 45° E., 169 lks. dist. A Pine, 24 ins. diam. brs. S. 43° E., 144 lks. dist. A Pine, 16 ins. diam. brs. S. 22° W., 135 lks. dist. A Pine, 10 ins. diam. brs. N. 67° W., 290 lks. dist.</p> <p>Land; surface mountainous. Soil; 3rd and 2nd rate, and part worthless. Good timber on W., 28 chs., some grass. Sec. 1 is nearly all well timbered, Tamarack, Fir, & Pine. Yew and alder underbrush.</p> <hr/> <p>S. 89° 33' W. on a true line bet. Secs. 2 & 11 Var. 20° 00' E.</p>	
3.00	Leave timber, N.W. and S.E.	
8.50	Gulch, opens S.	
40.30	Set basalt stone, 16 x 12 x 5 on steep S. Mountain side for ¼ Sec. Cor.	
80.60	Set pine post, 4 ins. sq., 4 ft. long in mound of stone on steep S. mountain side for cor. to Secs. 2, 3, 10 & 11.	
	Land; along line: steep mountain side	
	Soil; 3rd rate and worthless, some grass.	