

Subdivisional Lines of T 4 N., R. 37 E., W.M.

Chains		Feet
58.50	Gulch, opens N.W.	
80.00	<p>Set fir post in mound of stone, on steep W. hillside for Cor. to Secs. 4, 5, 8 & 9</p> <p>Land; surface steep mountain side</p> <p>Soil; 3rd rate.</p> <p>Some good timber in gulches, fir, tamarack and pine, but much of it already cut out.</p> <p>Good grass on open hillsides.</p>	
	E. on a random line bet. Secs. 4 & 9	
	Var. 14° 00' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
81.92	<p>Intersected N. & S. line, 324 lks. S. of Cor. to Secs. 3, 4, 9 & 10, from which Cor. I run</p> <p>S. 87° 42' W. on a true line bet. Secs. 4 & 9</p>	
	Var. 22° 00' E.	
3.50	Gulch, course S.	
9.00	On spur	
30.50	River bottom, course N.W. and S.E.	
35.00	Road up and down river, course N.W. and S.E.	
39.50	<p>Walla Walla River, 100 lks. wide, course from S.E. and runs due W. from this point for about 5.00 chs. I there- fore offset E. 25 lks. and at</p>	
39.25	<p>Set baslat stone, 18 x 10 x 5 in mound of stone on right bank of river for $\frac{1}{4}$ Sec. Cor.</p> <p>A cottonwood, 15 ins. diam. brs. S. 62° E., 147 lks dist.</p>	
46.50	Steep rocky bluff	
71.00	On spur, extends N.	
81.92	<p>The cor. to Secs. 4, 5, 8 & 9</p> <p>Land; surface very broken and mountainous.</p> <p>Soil; 3rd rate.</p> <p>Some 1st rate soil in river bottom, a few scattering trees along the line, Pine, Fir and Balm</p> <p>There is a farm and house on Sec. 4</p>	
	Aug. 28,	