

Subdivisional Lines of T 4 N., R 37 E., W.M.

| Chains | | Feet |
|--------|---|------|
| | <p>N. bet. Sec. 4 & 5 <div style="text-align: right;">Var. 14° 00' E.</div> </p> | |
| 21.50 | Gulch opens N.E. | |
| 30.50 | Walla Walla River, 75 lks. wide, course N.W. and Road. | |
| 40.00 | <p>Set basalt stone, 28 x 12 x 10 on steep rocky point for $\frac{1}{4}$ Sec. Cor.</p> | |
| 80.62 | <p>Set post in mound of stone, on S.E. face of bluff at in- tersection of 1st Standard Parallel N., 16.22 chs. W. of Standard Cor. to Secs. 32 & 33, for Cor. to Secs. 4 & 5.</p> | |
| | <p>Land; surface mountainous. Soil; 3rd rate and worthless. Small part on river, 1st rate. Some scattering timber, Pine, fir, tamarack, some grass.</p> | |
| | <p>N. bet. Secs. 17 & 18 <div style="text-align: right;">Var. 20° E.</div> </p> | |
| | Down along N.E. face of bluff | |
| 40.00 | <p>Set basalt stone, 14 x 12 x 4 on N.E. face of bluff for $\frac{1}{4}$ Sec. Cor. A fir, 22 ins. diam. brs. S. 85° E., 70 lks. dist. A fir, 6 ins. diam. brs. N. 74° W., 129 lks. dist.</p> | |
| 61.00 | Chouse Creek, 16 lks. wide, course N.W. | |
| 80.00 | <p>Set Tamarack post in mound of stone on steep S.W. face of bluff for Cor. to Secs. 7, 8, 17 & 18</p> | |
| | <p>Land; surface steep hillside Soil; 3rd rate and worthless. Some excellent timber in creek bottom and along S.W. bluff fir, tamarack, pine and balm. Good grass on open lands. Note:- I could find no trace of line to this mile, nor Cor. to Secs. 7, 8, 17 & 18. I therefore reset the Cor. to Secs. 7, 8, 17 & 18.</p> | |
| | <p>E. on a random line bet. Secs. 8 & 17 <div style="text-align: right;">Var. 27° 00' E.</div> </p> | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |