

Subdivisional Lines of T. 4 N., R. 37 E., W.M.

| Chains | | Feet |
|--------|---|------|
| | <p>W. $\frac{1}{2}$ mile is good farming land</p> <p>One of the witness trees is still standing, the other was cut down.</p> | |
| | <p>N. bet. Secs. 7 & 8</p> <p style="text-align: right;">Var. 27° 00' E.</p> | |
| 20.00 | On spur, extending W. | |
| 30.00 | In gulch, " " | |
| 40.00 | Set basalt stone, 14 x 10 x 5 on W. side of spur for $\frac{1}{4}$ Sec. Cor. | |
| 68.50 | Wagon road to Walla Walla, N.W. and S.E. | |
| 69.00 | Fence and field. | |
| 74.00 | Leave field, N.E. and S.W. | |
| 80.00 | Set pine post in mound of stone on plateau for cor. to Sec. 5, 6, 7 & 8 | |
| | Land: surface N. 20 chs. nearly level, S. 60 chs. mountainous. | |
| | Soil; N. 20 chs. Good 2nd rate; S. 60 chs. 3rd rate & stony. | |
| | Good bunch grass. N. 20 chs. good for farming. | |
| | Aug. 29. | |
| | <p>E. on a random line bet. Secs. 5 & 8</p> <p style="text-align: right;">Var. 22° 00' E.</p> | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.78 | Intersected N. & S. line, 324 lks. S. of Cor. to Secs. 4, 5, 8 & 9, from which Cor. I run | |
| | S. 87° 40' W. on a true line bet. Secs. 5 & 8 | |
| | Var. 14° 00' E. | |
| 4.50 | Gulch, course N.W. | |
| 18.00 | On spur, extends N. | |
| 27.00 | Gulch " " | |
| 40.39 | Set basalt stone, 18 x 12 x 3 on N. side of spur for $\frac{1}{4}$ Sec. Cor. | |
| | A Pine, 5 ins. diam. brs. S. 12° W., 76 lks. dist. | |
| 65.00 | No other trees. On table land, fence and field, course N.W. & S.E. | |