

Subdivisional Lines of T. 4 N., R. 37 E., W.M.

| Chains | | Feet |
|--------|--|------|
| | A pine, 48 ins. diam. brs. S. 8° 30' E., 73 lks. dist. marked T. 4 N., R. 37 E., S. 23 B.T. | |
| | A pine, 12 ins. diam. brs. S. 86° W., 106 lks. dist. marked T. 4 N., R. 37 E., S. 22, B.T. | |
| | From this Sec. Cor. I run | |
| | S. 89° 44' E. on a random line bet. secs. 14 and 23. | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 81.60 | Intersect N. and S. line, 60 lks. N. of the Cor. of Secs. 13, 14, 23 & 24, established by me, June 13, 1902. | |
| | Thence I run, | |
| | W. on a true line bet. Secs. 14 & 23 | |
| | Descend steep W. slope of mountain into Elbow Canyon. | |
| 9.25 | Enter timber, brs. N. and S. | |
| 9.50 | Foot of mountain, 500 ft. below Sec. Cor. | |
| 9.55 | Creek in Elbow Canyon, swift current, stony bottom, 10 lks. wide, course N. 10° W. | |
| 9.55 | Ascend E. slope of mountain | |
| 9.75 | Pack trail, brs. N. and S. | |
| 11.31 | Ravine, 25 ft. deep, course N. 60° W. | |
| 13.00 | Leave heavy timber, brs. N. and S. | |
| | Steeper ascent | |
| 41.60 | Set a basalt stone, 15 x 12 x 6 ins., 10 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on the N. face, from which | |
| | A pine, 28 ins. diam. brs. S. 88° W., 227 lks. dist. marked $\frac{1}{4}$ S 23 B T | |
| | A pine, 18 ins. diam. brs. N. 65° 30' W., 245 lks. dist. marked $\frac{1}{4}$ S. 14 B.T. | |
| 47.00 | Top of ridge, 1000 ft. above creek, brs. N. and S. | |
| | Descend into canyon. | |
| 49.00 | Enter heavy timber and dense undergrowth, brs. N. and S. | |
| 54.75 | Ravine, 15 ft. deep brs. N. 30° W. | |
| | Ascend over spur | |
| 57.25 | Top of spur, 50 ft. high, brs. N. and S. | |
| 69.00 | Ravine, 50 ft. deep, brs. N.W. | |
| 72.55 | Creek, 5 lks. wide, pure water, sandy bottom, course N. 10° E. | |
| | Ascend steep E. slope of ridge. | |
| 73.00 | Leave heavy timber, brs. N. and S., thence through very | |