

Subdivisional Lines of T 4 N R 38 E., W.M.

Chains		Feet
	N. bet. Secs. 28 & 29	
	Var. 20 3/4° E	
40.00	Set a post 3 1/2 ft. long, 3 ins. sq., with marked stone 24 ins. in ground for 1/4 Sec. Cor., marked 1/4 S. on W. face, from which:	
	A tamarack, 30 ins. diam. brs. N. 28° E., 62 lks. dist., marked 1/4 S B T	
	A fir, 20 ins. diam. brs. S. 25° W., 63 lks. dist. marked 1/4 S B T	
80.00	Set a fir post 4 1/2 ft. long, 4 ins. sq., with marked stone 24 ins. in ground for Cor. to Secs. 20, 21, 28 & 29, marked T 4 N S 21 on N.E., R 38 E S 28 on S.E., S. 29 on S.W., and S. 20 on N.W. faces with 2 notches on S. and 4 notches on E. edges, from which:	
	A fir, 10 ins. diam. brs. N. 61° E., 37 lks. dist. marked T 4 N R 38 E S 21 B T	
	A fir, 16 ins. diam. brs. S. 57° E., 37 lks. dist. marked T 4 N R 38 E S 28 B T	
	A fir, 8 ins. diam. brs. S. 60° W., 24 lks. dist. marked T 4 N R 38 E S 29 B T	
	A fir, 8 ins. diam. brs. N. 32° W., 51 lks. dist. marked T 4 N R 38 E S 20 B T.	
	Land; rolling	
	Densely covered with forests of tamarack, fir and pine	
	80 Chs.	
	Thick undergrowth; fir and buckbrush. 80.Chs.	
	Soil; good 2nd rate.	
	<hr/>	
	E. on random line bet. Secs. 21 & 28	
	Var. 20° E.	
40.00	Set temp. 1/4 Sec. Cor.	
79.60	Intersect N. and S. line, 40 lks. S. of Cor. to Secs. 21, 22, 27 & 28, thence I run	
	S. 89° 43' W. on true line bet. Secs. 21 & 28, with same Var.	
39.80	Set a post, 3 1/2 ft. long, 3 ins. sq., with marked stone 24 ins. in ground for 1/4 Sec. Cor., marked 1/4 S on N. face, from which:	
	A fir, 12 ins. diam. brs. S. 5° E., 102 lks. dist.	