

Supplemental Field Notes, Subdivisionals of T 4 N R 38 E., W.M.

Chains

Feet

No other trees available. Pits impracticable. I destroy the old $\frac{1}{4}$ Sec. Cor., and its witnesses.

The Cor. of Secs. 7, 8, 17 & 18

I find the witness trees in Secs. 18 & 7 to be as follows:

A fir, 12 ins. diam., brs. S. 50° W., 103 lks. dist.
and

A fir, 18 ins. diam., brs. N. $14\frac{1}{2}^{\circ}$ W., 156 lks. dist.,
marked as described in the original notes.

Cor. of Secs. 5, 6, 7 & 8

I find the bearing trees in Secs. 8, 7, 6 to be as follows:

A pine, 8 ins. diam. brs. S. $30\frac{1}{2}^{\circ}$ E., 109 lks. dist.
and

A pine, 30 ins. diam. brs. S. $27\frac{1}{2}^{\circ}$ W., 221 lks. dist.

A pine, 16 ins. diam., brs. N. $56\frac{1}{2}^{\circ}$ W., 122 lks.
dist.

Note: through a clerical error, these bearing trees were reported incorrectly in my original notes.

Retrace $W\frac{1}{2}$ of line bet. Secs. 7 & 18

From the Cor. of Secs. 7, 12, 13 & 18, I retrace
N. $89^{\circ} 54'$ E. bet. Secs. 7 & 18

39.35 Intersect $\frac{1}{4}$ Sec. Cor.

Note: The original notes in my returns for the survey of this Tp. should be corrected in accordance with these supplemental notes.

Robert F. Omeg.
U.S. Deputy Surveyor.

April 9, 1906.

In accordance with letter, dated April 25, 1907, of U.S. Surveyor General for Oregon, and letter E., dated April 15, 1907, of the Assistant Commissioner of the General Land Office, I proceed to make corrections in the field of the survey of Tp. 4 N R 38 E, W.M., under my contract