

Dependent Resurvey of Part of S. Bdy. of T 4 N., R. 38 E.,

Chains		Feet
44.05	Highway, (Tollgate to Elgin), brs. N. 30° W. and S. 30° E.	
66.06	Ridge, brs N. and S.; desc. 88 ft. over SW. slope.	
72.60	Dirt road, brs. N. 20° W. and S 20° E	
80.80	The cor. of secs. 32 & 33 only, determined by reference to the record distances to the original bearing trees.	
	At point for cor.	
	Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for Cor. of Secs. 32 & 33 only, with brass cap marked	
	T4NR38E S32 S33 T3NR38E S 5 1939	
	from which	
	A pine, 20 ins. diam., brs. N. 50½° E., 15 lks. dist., marked T 4 N R 38 E S 33 B T (Old B.T.)	
	A tamarack, 12 ins. diam., brs. N. 61° W., 30 lks. dist., marked T 4 N R 38 E S 32 B T. (Old B.T.)	
	Land; mountainous Soil; rocky loam; 3rd rate. Timber, fir, pine, spruce, tamarack, and yew. Undergrowth, alder, huckleberry, willow, and buckbrush.	
	N. 89° 56' W., along the S. Bdy. of sec. 32.	
	Desc. 50 ft. over SW. slope, through heavy timber and dense undergrowth.	
5.08	Fence, brs. N. and S.	
6.95	Leave heavy timber and dense undergrowth, brs. N. and S.; enter swamp, brs. N. and S.	
89.10	Leave swamp, brs. N. and S.; enter heavy timber and dense undergrowth, brs. N. and S.; asc. 66 ft. over gradual E. slope	
9.15	Barn, brs. S., about 2.50 Chs. dist.	
25.90	Round topped spur, slopes N; desc. 35 ft. over gradual NW. slope.	
34.20	Creek, 3 lks. wide, course N.: asc. 33 ft. over NE. slope.	
40.44	The ¼ Sec. Cor. of Sec. 32 only, determined by reference to the record bearings and distances to the original bearing trees.	
	At point for Cor.	
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for ¼ Sec. Cor. of Sec. 32 only, with brass cap marked	
	¼ S 32 _____ 1939	
	from which	
	A dead pine, 15 ins. diam., brs. N. 15° E., 12 lks. dist., marked ¼ S B T. (Old B.T.)	