


Dependent Resurvey of Part of Subdivisions of T 4 N R 38 E.

Chains		Feet
	A spruce, 16 ins. diam., brs. S. 22° E., 191 lks. dist., marked $\frac{1}{4}$ S 31 B T. (New B.T.)	
	Thence	
	S. 89° 51' E., continuing measurements.	
	Asc. 134 ft. over SW. slope.	
51.25	Telephone line, brs. NW. and SE.	
52.00	Cabin, brs. S., about 1.50 chs. dist.	
53.55	Cabin, brs. S., about 3.00 chs. dist.	
55.10	McIntyre Lookout Road, brs. NW. and SE.	
62.70	Flat topped ridge, brs. N. and S.; desc. 80 ft. over E/ slope.	
66.70	Dirt road, brs. N. and S.	
79.19	The cor. of Secs. 29, 30, 31, and 32, heretofore described.	
	Land; rolling and mountainous. Soil; sandy loam; 2nd rate. Timber, fir, pine, spruce, and tamarack. Undergrowth, alder, willow, vinemaple, and huckleberry.	
	N. 0° 08' W., bet. Secs. 29 & 30.	
	Over rolling land, through heavy timber and dense undergrowth.	
20.00	Creek, 2 lks. wide, course E.	
21.00	Cabin, brs. W., about 0.80 Chs. dist.	
25.50	Creek, 2 lks. wide, course E.	
27.00	Cabin, brs. E., about 0.50 chs. dist.	
28.00	Creek; 1 lks. wide, course E.	
30.50	Cabin, brs. E., about 2.00 chs. dist.	
31.50	Cabin, brs. E., about 4.00 chs. dist.	
31.70	Dirt road, brs. NE. and SW.	
40.27	Proportionate measurement.	
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., with brass cap marked	
		
	from which	
	A spruce, 34 ins. diam., brs. S. 41° E., 5 lks. dist., marked $\frac{1}{4}$ S 29 B T.	
	A spruce, 26 ins. diam., brs. N. 50° W., 12 lks. dist., marked $\frac{1}{4}$ S 30 B T.	
50.55	House, brs. E., about 8.00 chs. dist.	
50.85	Old sawmill, brs. E., about 5.00 chs. dist.	