

Dependent Resurvey of Part of Subdivisions of T 4 N R 38 E.

Chains		Feet
80.54	<p>The cor. of secs. 19, 20, 29, and 30, which is a basalt stone, 15 x 10 x 10 ins., firmly set, marked with 5 grooves on E. and 2 grooves on S. face.</p> <p>At point for cor.</p> <p>Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with the original stone deposited at the base, for cor. of secs. 19, 20, 29, and 30, with brass cap marked</p> <div style="text-align: center;"> <p>T4NR38E S19 S20 S30 S29 1939</p> </div> <p style="text-align: right;">from which</p> <p>A burned and fallen tamarack, 14 ins. diam., brs. N. 67°E., 17 lks. dist., marks burned off. (Old B.T.)</p> <p>A burned and fallen fir, 20 ins. diam., brs. S. 30° E., 26 lks. dist., marks burned off. (Old B.T.)</p> <p>A pine, 20 ins. diam., brs. N. 89½°E., 24 lks. dist., marked T 4 N R 38 E S 20 B T. (New B.T.)</p> <p>A tamarack, 16 ins. diam., brs. N. 89½°W., 15 lks. dist., marks grown over. (Old B.T.)</p> <p>A tamarack, 16 ins. diam., brs. N. 84½°E., 24 lks. dist., marked T 4 N R 38 E S 20 B T. (New B.T.)</p> <p>A fir, 14 ins. diam., brs. S. 58° E., 63 lks. dist., marked T 4 N R 38 E S 29 B T. (New B.T.)</p> <p>Land; rolling Soil; sandy loam; 2nd rate. Timber; fir, pine, spruce, and tamarack. Undergrowth, alder, willow, vinemaple, and huckleberry.</p>	
	<p>From the Cor. of Secs. 20, 21, 28, and 29, heretofore described.</p>	
	<p>N. 89° 34' W., bet. Secs. 20 & 29.</p>	
	<p>Asc. 10 ft. over gradual E. slope, through heavy timber and dense undergrowth.</p>	
19.50	<p>Top of ascent, brs. N. and S.; desc. 30 ft. over W. slope.</p>	
25.80	<p>Leave heavy timber and dense undergrowth, brs. N. and S.; enter swamp, brs. N. and S.</p>	
33.80	<p>Leave swamp, brs. N. and S.; enter heavy timber and dense undergrowth, brs. N. and S.; asc. 59 ft. over E. slope.</p>	
40.01	<p>The ¼ sec. cor., which is a basalt stone, 12 x 8 x 7 ins., firmly set, marked ¼ on N. face.</p> <p>At point for cor.</p> <p>Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the original stone deposited at the base, for ¼ sec. cor., with brass cap marked</p>	
	<div style="text-align: center;"> <p>¼ S 20 ¼ S 29 1939</p> </div>	from which